

**OWNER:**

Laramie County Public Works  
Don Beard  
307-633-4302

**ENGINEER:**

USDA Natural Resources  
Conservation Service  
Blane Christopherson  
307-233-6742

**CONTRACT AMOUNT:**

\$1.8 million

**PROJECT START:**

December 2008

**PROJECT COMPLETION:**

May 2009

**CONTRACT TYPE:**

Unit Price, Hard Bid

**CRI PROJECT MANAGER:**

Dave Simpson

**CRI SITE MANAGER:**

Clay Crisp

**CRI ON-SITE SUPERVISION:**

Shawn O'Mara—Earthwork

**UNIQUE JOB ELEMENTS:**

Completed on time and within  
budget under very extreme  
conditions

**MATERIAL QUANTITIES:**

154,000 CY Unclassified Ex  
5,000 CY Rip Rap  
775 LF Structural Plate Arch  
3 months dewatering

**WORK PERFORMED IN HOUSE:**

90% of CRI Contract



This project was constructed for Laramie County Public Works. Connell Resources performed the earthwork, erosion control, structural plate pipe arch installation, and all dewatering for this project. The project was to construct a 3600' flood control channel ranging from 12' - 18' deep with a 50' bottom and 3:1 side slopes.

