

OWNER:

City of Laramie
Katharine Trowbridge
307-760-5629

ENGINEER:

WWC Engineering
Stan Miller
307-742-0031

CONTRACT AMOUNT:

\$ 1.0 Million

PROJECT START:

May 2010

PROJECT COMPLETION:

July 2010

CONTRACT TYPE:

Unit Price

CRI PROJECT MANAGER:

Dan Giesler

CRI SITE MANAGER:

Curtis Rogers

MATERIAL QUANTITIES:

- 18" PVC Waterline 638'
- 8" PVC Waterline 2937'
- 85 EA Services
- 8" Sanitary Sewer 1100'
- 1000 Tons Asphalt Paving
- 8000 Tons Aggregate Base

WORK PERFORMED IN HOUSE:

80% of CRI's contract
Performed in house



This project includes the replacement of five separate segments of existing water mains and all appurtenances including but not limited to valves, services, and hydrants involving a total length of 3800' of water main. Three of the five segments were down 12' wide alleys. Work also includes full reconstruction of 930 feet of residential street, including curbs, gutters and sidewalks and 500 feet of new storm drains, with inlets and manholes. Excavation and resurfacing of approximately 1,930 feet of alleys. Project also included 1100' of 8" sanitary sewer which had to be by-passed for the duration of the installation.

